BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of work:Estimate for Providing Concreate Roads in Amruthahalli S.C Colony 8th and 9th CrossRoads in ward No. 07, Byatarayanapura Kodigehalli Sub Division.

ordinary soil.

								Estimate Cost Rs.	1050000.00
Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 300-1. Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. No. 138 Item No. 19.2/ PWD SR 2014-15.								
	Disiliting of Sc Colony Roads Towards Southern Side								
	F 8th Coss Amruthahlli SC Colony		2	15.00	0.30	0.40	3.60		
	G 9th Coss Amruthahlli SC Colony		2	57.00	0.30	0.40	13.68		
	H 10th Coss Amruthahlli SC Colony		2	22.00	0.30	0.40	5.28		
	Disiliting of Sc Colony Roads Towards Southern Side For Roads								
	F 8th Coss Amruthahlli SC Colony		1	15.00	3.00	0.20	9.00		
	G 9th Coss Amruthahlli SC Colony		1	57.00	6.00	0.20	68.40		
	H 10th Coss Amruthahlli SC Colony		1	22.00	3.00	0.20	13.20		
							113.16	105.84	11977.00
	Basic Rate	98.00	70						
	Area Weightage @ 8%	7.84	5.6						8554.89
	Total	105.84	75.6						
2	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. (P. 145, I.No. 19.64) SR-2014-15								
	Disiliting of Sc Colony Roads Towards Southern Side								
	F 8th Coss Amruthahlli SC Colony		1	15.00	6.30		94.50		
	G 9th Coss Amruthahlli SC Colony		1	57.00	6.40		364.80		
	H 10th Coss Amruthahlli SC Colony		1	22.00	6.30		138.60		
							597.90	4.482	2680.00
	Basic Rate	4.15							
	Area Weightage @ 8%	0.332							
	Total	4.482							
3	KSRRB 300-64.2. Extra for watering the earth to bring the earth upto required optimum moisture content with mechinery including cost of all labour, HOM of machineries complete as per specifications. (P. 146, I.No. 19.72) SR-2014-15								
	Disiliting of Sc Colony Roads Towards Southern Side For Roads								
	F 8th Coss Amruthahlli SC Colony		1	15.00	6.30	0.20	18.90		
	G 9th Coss Amruthahlli SC Colony		1	57.00	6.40	0.20	72.96		
	H 10th Coss Amruthahlli SC Colony		1	22.00	6.30	0.20	27.72		
							119.58	**2.16**	**258.00**
	Basic Rate	**2.00**							
	Area Weightage @ 8%	**0.16**							
	Total	**2.16**							
4	KSRB 4-1.3 Providing and laying cement concrete using 40mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges) Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-341 Kg/cum) (P. 12, I.No. 4.3) SR-2014-15								
	Disiliting of Sc Colony Roads Towards Southern Side For Roads								
	F 8th Coss Amruthahlli SC Colony		1	15.00	6.30	0.15	14.18		
	G 9th Coss Amruthahlli SC Colony		1	57.00	6.40	0.15	54.72		
	H 10th Coss Amruthahlli SC Colony		1	22.00	6.30	0.15	20.79		
							89.69	4847.04	**434707.00**
	Basic Rate	4488							
	Area Weightage @ 8%	359.04							
	Total	4847.04							

5	Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges) Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (P. 18, I.No. 4.49.1) SR-2014-15								
	Disiliting of Sc Colony Roads Towards Southern Side For Roads								
	F 8th Coss Amruthahlli SC Colony		1	15.00	6.30	0.10	9.45		
	G 9th Coss Amruthahlli SC Colony		1	57.00	6.40	0.10	36.48		
	H 10th Coss Amruthahlli SC Colony		1	22.00	6.30	0.10	13.86		
							59.79	5847.12	**349599.00**
	Basic Rate	5414							
	Area Weightage @ 8%	433.12							
	Total	5847.12							
6	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift. (P. 171 I. No. 22.7) SR-2014-15								
	Disiliting of Sc Colony Roads Towards Southern Side For Roads								
	F 8th Coss Amruthahlli SC Colony		1	15.00	6.30		94.50		
	G 9th Coss Amruthahlli SC Colony		1	57.00	6.40		364.80		
	H 10th Coss Amruthahlli SC Colony		1	22.00	6.30		138.60		
							597.90	97.20	**58116.00**
	Basic Rate	90.00							
	Area Weightage @ 8%	7.2							
	Total	97.2							
7	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. for concrete pavement(P. 172 I. No. 22.8.1) SR-2014-15								
	SC Colony Amruthahlli	Rmtr	20	4.50			90.00		
							90.00	124.20	11178.00
	Basic Rate	115							
	Area Weightage @ 8%	9.2							
	Total	124.2							
8	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (P. 5, I.No. 2.3) SR-2014-15						Cum		
	C.D.1 No		1	8.00	1.80	0.90	12.96		
							12.96	176.04	2281.00
	Basic Rate	163.00							
	Area Weightage @ 8%	13.04							
	Total	176.04							
9	KSRB 4-1.2: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P. 12, I.No. 4.2) SR-2014-15						Cum		
	C.D.1 No		1	8.00	1.80	0.90	12.96		
							12.96	5064.12	65631.00
	Basic Rate	4689.00							
	Area Weightage @ 8%	375.12							
	Total	5064.12							

10	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (P. 23, I.No. 5.6) SR-2014-15						Cum		
	C.D.1 No		1X2	8.00	0.60	0.60	5.76		
							5.76	3836.16	22096.00
	Basic Rate	3552.00							
	Area Weightage @ 8%	284.16							
	Total	3836.16							
11	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 (P 16, I.No 4.28) SR-2014-15						Sqm		
	C.D.1 No		1	8.00	0.60		4.80		
	Side		2	6.00	0.23		2.76		
			2	1.80	0.23		0.83		
							8.39	236.52	1984.00
	Basic Rate	219.00							
	Area Weightage @ 8%	17.52							
	Total	236.52							
12	Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum) (P. 18, I.No. 4.49.1) SR-2014-15						Cum		
	C.D.1 No		1	8.00	1.80	0.23	3.31		
							3.31	5847.12	19366.00
	Basic Rate	5414.00							
	Area Weightage @ 8%	433.12							
	Total	5847.12							
13	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P. 17, I.No. 4.46) SR-2014-15						Qtl		
	TMT Bars Fe 415, 500, 550	6834,							
	C.D.1 No		1	8.00	1.80	0.23	3.31		
							3.31		
	3.31x180Kg/Cum						595.80		
							0.59	78351.84	46228.00
	Basic Rate	72548.00							
	Area Weightage @ 8%	5803.84							
	Total	78351.84							
14	KSRB 15.1.3 – do – Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. (P.109.I.No. 15.3) SR-2014-15						Sqm		
	C.D.1 No		4	8.00		0.60	19.20		
							19.20	92.88	1783.00
	Basic Rate	86.00							
	Area Weightage @ 8%	6.88							
	Total	92.88							

15	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km (Page No.141)								
		Cum	Qty. Vide Item No. 1				113.16		
							113.16	81.00	9166.00
	Basic Ratefor haulage of materials as per item	12.8							
	Average weight of earth 1.28 tonne/Kg for	62.2							
	Add loading and unloading vide item No. 17.1	75							
	Area Weightage @ 8%	6							1033628.00
	Total	81							
	Sub total								1037050.00
16	Third party inspection charges 1%								10371.00
17	Miscesallaneous Charges	L/S							2579.00
								Total	1050000.00

10336
6036.

(Rupees Ten Lakh Fifty Thousand Only)

CERTIFICATE:

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per PWD SR of 2014-15.
3 The provisions were made in this estimate are necessary and adequate.
4 This works come under B.B.M.P. limits.

Junior Engineer

Assistant Executive Engineer
Bruhat Bangalore Mahanagara Palike
Kodigehalli Sub Division

Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Division

Sanction for Rs.....
Administrative Approval
Accorded for Rs 10.50 lakh Rs.
is accorded under head.....
P1878
.....
registered as CE No. 132 Dt: 11.02.15 Subject
to Conditions contained in enclosed memo
No...../.....Dt.....
AE/EE TA SE (BTP) CE (BTP)
(YNK)

Technical Sanction for Rs. 10.50 Lakhs.
Ten Lakhs Fifty Thousand only.
P-1878.
Registered as EE No. 60 Dated..... Subject
to conditions contained enclosed memo.
No...../ 354. Dt. 11/02/15
11/02
AE/JE
EE (BTP.Div.)

LAY-OUT PLAN FOR THE AMRUTHAHALLI S.C. COLONY. IN WARD NO 7 BYATARAYANAPURA